

Inverter Kit



Inverter Kit

Item No. SREInverterKit



| SRE InverterKit | Solar System Size (Inverter accomodates) | TXMAS FSS Price |
|-----------------|------------------------------------------|-----------------|
| 2-4kW | 2-4 kW grid-tied | \$4,991.62 |
| 4-6kW | 4-6 kW grid-tied | \$6,531.20 |
| 6-8kW | 6-8 kW grid-tied | \$8,705.27 |
| 8-10kW | 8-10 kW grid-tied | \$11,020.66 |
| 10-15kW | 10-15 kW grid-tied | \$13,351.08 |
| 16-20kW | 16-20 kW grid-tied | \$18,929.07 |
| 21-24kW | 21-24 kW grid-tied | \$20,207.04 |
| 25-32kW | 25-32 kW grid-tied | \$31,077.35 |
| 25-32kW* | 25-32 kW grid-tied | \$42,639.26 |
| 33-48kW | 33-48 kW grid-tied | \$38,128.76 |
| 33-48kW* | 33-48 kW grid-tied | \$52,472.15 |
| 49-76kW | 49-76 kW grid-tied | \$79,880.96 |
| 77-110kW | 77-110 kW grid-tied | \$94,134.14 |

*B = the alternative inverter selection; utilizes one large inverter versus numerous smaller inverters



SREInverterKit SYSTEM SPECS

| | |
|-----------------------------|------------------------------------------------------------------|
| System Size | Sold in relation to the SREModular-BG/MS/SH/CP system purchased |
| Minimum Inverter Size Order | Inverter size must accommodate the SREModular-BG/MS/SH/CP system |
| Grid Voltage and Phase | Inverters are designed to meet any grid voltage and phase |

SREInverterKit SYSTEM INCLUDES

| | |
|---------------------------------|---------------------------------------------------------------------|
| Inverter Type | Grid-tied inverter |
| Number of Inverters | System specific |
| Mounting Hardware | All necessary mounting hardware is included |
| Space Needed per SREInverterKit | System specific - up to approximately 6' x 4' x 6' (144 Cubic feet) |
| DC Disconnect Switch | Includes DC disconnect switch with fuses |
| Copper Wiring | Includes wiring for array to inverter wiring |
| Wire Terminations | Includes all wire terminations |
| MC Extension Cable | Included |
| Lighting Arrestor | Includes A/C and D/C lighting arrestor |
| Line Side Tap | Includes enclosure with terminal block and conduit connections |
| Combiner Box | Included |
| Flex | Included |
| Fittings | Included |
| Manufacturer's Documentation | Included |

ADDITIONAL EQUIPMENT REQUIRED FOR SYSTEM COMPLETION (Not Included with SREInverterKit)

| | |
|------------------------|---------------------------------------------------------|
| SREModular-BG/MS/CP/SH | All SREModulars are scalable to fit any available space |
| Installation Labor | Labor is factored at a pre-determined rate |

SUGGESTED UPGRADES

| | |
|-----------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| SREInverterMonitorKit | My.SRE3.com monitors your system's PV production and your building's energy consumption and provides data updates throughout the day. This information is available and accessible anywhere via the Internet. Track the history of your system and showcase this information from a flat screen for all to see. |
|-----------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|

ADDITIONAL NOTES

This grid tied solar photovoltaic inverter kit should be coupled with the appropriate SREModular kit.

PURCHASE INSTRUCTIONS

Contact Standard Renewable Energy by phone (877) 923-7733 or e-mail at gov@sre3.com.